



Proposal

Proposal Submitted to:
Albany County DPW

September 21, 2022

Attention: Lisa Ramundo

Re: Knox Sub-Division Fueling Station

Environmental & Fueling Systems L.L.C. to provide all necessary equipment, materials, and labor to perform the following:

Scope of Work: W / Roles & Responsibilities

- E&FS will disconnect, remove, and set aside for re-use the existing Wayne Pump w/stainless steel stand and Fuel Master fuel management system control unit and pedestal.
- Albany Co will provide safe storage for the Wayne Pump and Fuel Master Controller.
- Albany County will provide the removal and disposal of the roof structure over the existing tank dike location.
- E&FS will provide equipment and labor to pump out and clean the existing 1,000gallon gasoline and 2,000gallon diesel tanks.
- Albany Co will provide equipment to lift and set tanks on flatbed for transportation and disposal.
- E&FS will provide a full set of CAD drawings for the proposed fueling station, including electrical layout, pump layout and tank design and layout.
- Albany County will provide all site work including the tank pad, drive on pad, vehicle impact protection for the tank / pump field.
- E&FS recommends the County provide a 100 Amp service panel for fueling station located on adjacent outside wall or as close as possible to the new fuel station.
- E&FS will provide all conduit and wiring from panel board to tank field, including Power Integrity Panel and Emergency Stop points located in compliance with NFPA 70.



Scope of Work: W / Roles & Responsibilities (Cont.)

- E&FS will provide a new 4,000gallon split compartment (2500g/1500g) FireGuard Aboveground tank by Highland Tank Mfg. Co including ladder and step off platform.
- E&FS will provide all tank accessories for a compliant fueling system, including all vents, valves, and fittings.
- E&FS will provide (2) 10gallon remote fill/spill containments with 2" steel piping to tank fill ports.
- E&FS will re-install existing Wayne pump with stainless steel stand using 1.5" black steel piping.
- E&FS will provide and install one heat trace circuit with controller for diesel fuel piping up to 75lf.
- E&FS will provide and install insulation w/PVC jacket for diesel fuel piping.
- E&FS will provide and install an Omntec OEL8000IIK4P Proteus Electronic Tank Level and Leak Detection System including all electrical conduit and wiring.
- E&FS will re-install existing Fuel Master fuel management system.
- Albany County will provide a desk top PC or a server switch for Fuel Master data base.
- E&FS will start up all equipment and test for tightness and proper functionality.
- E&FS will provide O&M Manuals for installed equipment.

Quotation:

Project Cost: \$170,845.00



Notes, Conditions & Assumptions:

1. *The above price will be held for 30 days from the date of this quotation. Thereafter it may be subject to change without notice.*
2. *Permits to be provided by others.*
3. *This quotation includes prevailing wage scale labor.*
4. *This quotation reuses existing Wayne Pump and Fuel Master fuel management system*
5. *This quotation assumes both fuel storage tanks will be drawn down to lowest point before removal work begins.*
6. *This quotation does not include a tank support pad, vehicle drive on pad, or vehicle impact protection for the tank field.*
7. *This quote does not include any lighting at the fuel station location.*
8. *This quote does not include any fuel for tanks.*

Terms and Signatures:

Terms: According to Contract Documents

ACCEPTANCE OF *PROPOSAL / CONTRACT*

The above specification, notes, terms, and contract conditions are satisfactory, and (I/We) hereby authorize the performance of this work. This contract is VOID 30 days from the date above.

Signature _____ Date _____

Thank you for your consideration

Sincerely,

Tony Isgro

Tony Isgro
Environmental & Fueling Systems, LLC
Sales / Estimating
Desk: 518.272.8142 x 163
Mobile: 518.817.5934
Fax: 518.237.0498