

COUNTY OF ALBANY

**COUNTY ROAD 352 (FOX CREEK ROAD) OVER FOX CREEK
BRIDGE REPLACEMENT PROJECT**

RFB-2022-130

ADDENDUM #2

December 7, 2022

The following Addendum No. 2 consisting of thirteen (13) pages (including this cover page) is hereby issued on the 7th day of December 2022, in connection with the Request for Bids 2022-130 as requested by the Albany County Department of Public Works.

COUNTY OF ALBANY

RFB-2022-130

**COUNTY ROAD 352 (FOX CREEK ROAD) OVER FOX CREEK BRIDGE
REPLACEMENT PROJECT**

ADDENDUM #2

The following information is provided as a result of a question(s) posed by vendor(s):

ITEM #1: The final grading plan and excavation plan show the slope at the northwest corner being excavated and re-graded which will require the removal of the trees in this area. Please advise if an item for clearing and grubbing will be added to the contract or if the county will be removing these trees prior to construction beginning.

Response #1: A clearing and grubbing item was not included in the contract and will not be added. The contractor is responsible for any necessary tree removals or grubbing required to complete the work. Include the cost in the bid prices for various other items in the contract. The contract is bid as a lump sum contract as indicated in the Bid Form.

Note that the unit prices for Items 697.03, 698.04, 698.05, and 698.06 were not completed on the Bid Schedule. A revised Bid Schedule is provided with \$1.00 as the unit price for these items.

ITEM #2: The plans show relocation of the power lines to the downstream side of this project and new pole locations were observed during a site visit. Please confirm the schedule of this work and if it is anticipated to be completed prior to commencement of construction.

Response #2: All utilities will be temporarily relocated or removed during construction to avoid conflicts with construction. Central Hudson Gas & Electric will drop 2 spans of wire from pole k25657-k25658-k25659 and remove pole k25658. Mid-Hudson Cable will drop their cable during construction and provide service from the other side of the bridge. Verizon will place a service wire off VZ pole 15 and run it along the highway boundary to new VZ pole set across the street from VZ pole 17. Their cable will be removed during construction. All utilities have confirmed that their utilities will be removed or relocated prior to March 2023.

ITEM #3: Will plant inspection of the Reinforced Concrete Span units be required? Additionally, please provide scope of testing required by the contractor's third party inspector.

Response #3: Plant inspection of the reinforced concrete span units is required and shall be provided for by the contractor. Include the cost of the plant inspection in the unit price of the precast units.

The contractor will be responsible for providing inspection for items marked "X" in the Field column as indicated on 01340-4 (page 178) in the Project Manual. This includes, but is not necessarily limited to, earthwork and aggregate sampling and testing, and concrete sampling and testing.

End of Addendum #2

Brought Forward \$ _____.

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
202.120001	REMOVING EXISTING SUPERSTRUCTURES	1	LS	_____	Dollars	\$ _____.	\$ _____.
					Cents		
202.19	REMOVAL OF SUBSTRUCTURES	348	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
203.02	UNCLASSIFIED EXCAVATION AND DISPOSAL	423	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
203.03	EMBANKMENT IN PLACE	2389	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
203.07	SELECT GRANULAR FILL	33	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
203.21	SELECT STRUCTURE FILL	720	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
203.24010017	SHOULDER BACKUP MATERIAL	24	TON	_____	Dollars	\$ _____.	\$ _____.
					Cents		

Page Total \$ _____

Carry Forward \$ _____

Brought Forward \$ _____.

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
206.01	STRUCTURE EXCAVATION	3253	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
206.0201	TRENCH AND CULVERT EXCAVATION	176	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
207.21	GEOTEXTILE SEPARATION	67	SY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
207.26	PREFABRICATED COMPOSITE STRUCTURAL DRAIN	248	SY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
209.13	SILT FENCE-TEMPORARY	450	LF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
304.12	SUBBASE COURSE, TYPE 2	255	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
402.098304	9.5 F3 TOP COURSE HMA, 80 SERIES COMPACTION	63	TON	_____	Dollars	\$ _____.	\$ _____.
					Cents		

Brought Forward \$ _____.

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
402.198904	19 F9 BINDER COURSE HMA, 80 SERIES COMPACTION	110	TON	_____	Dollars	\$ _____.	\$ _____.
					Cents		
402.378904	37.5 F9 BASE COURSE HMA, 80 SERIES COMPACTION	180	TON	_____	Dollars	\$ _____.	\$ _____.
					Cents		
407.0102	DILUTED TACK COAT	96	GAL	_____	Dollars	\$ _____.	\$ _____.
					Cents		
418.7603	ASPHALT PAVEMENT JOINT ADHESIVE	60	LF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
551.11	CAST-IN-PLACE CONCRETE PILES	3990	LF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
551.13	FURNISHING EQUIPMENT FOR DRIVING PILES	1	LS	_____	Dollars	\$ _____.	\$ _____.
					Cents		
551.14	DYNAMIC PILE TESTING	2	EACH	_____	Dollars	\$ _____.	\$ _____.
					Cents		

Brought Forward \$ _____.

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
552.13	TEMPORARY STEEL SHEETING	2220	SF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
553.010001	COFFERDAMS (TYPE 1)	2	EACH	_____	Dollars	\$ _____.	\$ _____.
					Cents		
553.030001	TEMPORARY WATERWAY DIVERSION STRUCTURE	1	EACH	_____	Dollars	\$ _____.	\$ _____.
					Cents		
553.030002	TEMPORARY WATERWAY DIVERSION STRUCTURE	1	EACH	_____	Dollars	\$ _____.	\$ _____.
					Cents		
555.08	FOOTING CONCRETE, CLASS HP	158	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
555.09	CONCRETE FOR STRUCTURES, CLASS HP	58	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
556.0201	UNCOATED BAR REINFORCEMENT FOR CONCRETE STRUCTURES	19200	LB	_____	Dollars	\$ _____.	\$ _____.
					Cents		

Brought Forward \$ _____.

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
556.0202	EPOXY-COATED BAR REINFORCEMENT FOR STRUCTURES	3600	LB	_____	Dollars	\$ _____.	\$ _____.
					Cents		
562.0101	REINFORCED CONCRETE SPAN UNITS	164	SY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
568.51	STEEL BRIDGE RAILING (FOUR RAIL)	91	LF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
568.70	TRANSITION BRIDGE RAILING	128	LF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
595.50000018	SHEET-APPLIED WATERPROOFING MEMBRANE	2000	SF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
603.6013	REINFORCED CONCRETE PIPE CLASS III, 60 INCH DIAMETER	42	LF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
603.7313	REINFORCED CONCRETE PIPE END SECTIONS 60 INCH DIAMETER	1	EACH	_____	Dollars	\$ _____.	\$ _____.
					Cents		

Brought Forward \$ _____.

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
606.10	BOX BEAM GUIDE RAILING	412	LF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
606.120201	BOX BEAM GUIDE RAILING END ASSEMBLY, TYPE IIA	4	EACH	_____	Dollars	\$ _____.	\$ _____.
					Cents		
606.73	REMOVING AND DISPOSING BOX BEAM GUIDE RAILING	585	LF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
610.16010020	TURF ESTABLISHMENT - PERFORMANCE	228	SY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
613.04000001	STOCKPILING AND PLACING EXISTING STREAM BED MATERIALS	339	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
619.01	BASIC WORK ZONE TRAFFIC CONTROL	1	LS	_____	Dollars	\$ _____.	\$ _____.
					Cents		
619.04	TYPE III CONSTRUCTION BARRICADE	16	EACH	_____	Dollars	\$ _____.	\$ _____.
					Cents		

Brought Forward \$ _____.

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
619.1711	TEMPORARY POSITIVE BARRIER - CATEGORY 1 (PINNING PROHIBITED)	66	LF	_____	Dollars	\$ _____.	\$ _____.
					Cents		
620.04	STONE FILLING (MEDIUM)	225	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
620.06010002	EXTRA HEAVY RIP-RAP	202	TON	_____	Dollars	\$ _____.	\$ _____.
					Cents		
620.0801	BEDDING MATERIAL, TYPE 1	41	CY	_____	Dollars	\$ _____.	\$ _____.
					Cents		
625.01	SURVEY OPERATIONS	1	LS	_____	Dollars	\$ _____.	\$ _____.
					Cents		
637.11	ENGINEER'S FIELD OFFICE - TYPE 1	6	MNTH	_____	Dollars	\$ _____.	\$ _____.
					Cents		
645.5102	GROUND-MOUNTED SIGN PANELS LESS THAN OR EQUAL TO 32 SF, WITH Z-BARS	9	SF	_____	Dollars	\$ _____.	\$ _____.
					Cents		

Brought Forward \$ _____

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
645.81	TYPE A SIGN POSTS	1	EACH	_____	Dollars	\$ _____	\$ _____
					Cents		
646.22	DELINEATOR, SNOWPLOWING MARKER, SUPPLEMENTARY SNOWPLOWING MARKER PANELS	6	EACH	_____	Dollars	\$ _____	\$ _____
					Cents		
646.32	STEEL POST, 2.0 LB/FT	4	EACH	_____	Dollars	\$ _____	\$ _____
					Cents		
647.61	REMOVE AND DISPOSE SIGNS, GROUND MOUNTED TYPE A SIGN SUPPORTS AND FOUNDATIONS - SIZE 1 (UNDER 30 SQUARE FEET)	1	EACH	_____	Dollars	\$ _____	\$ _____
					Cents		
685.11	WHITE EPOXY REFLECTORIZED PAVEMENT STRIPES - 20 MILS	400	LF	_____	Dollars	\$ _____	\$ _____
					Cents		
685.12	YELLOW EPOXY REFLECTORIZED PAVEMENT STRIPES - 20 MILS	420	LF	_____	Dollars	\$ _____	\$ _____
					Cents		
697.03	FIELD CHANGE PAYMENT	96600	DC	<u>FIXED PRICE SPECIFICATION</u>	Dollars	\$ <u>1.00</u>	\$ <u>96,600.00</u>
					Cents		

Brought Forward \$ _____

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
698.04	ASPHALT PRICE ADJUSTMENT	700	DC	<u>FIXED PRICE SPECIFICATION</u>	Dollars	\$ <u>1.00</u>	\$ <u>700.00</u>
					Cents		
698.05	FUEL PRICE ADJUSTMENT	800	DC	<u>FIXED PRICE SPECIFICATION</u>	Dollars	\$ <u>1.00</u>	\$ <u>800.00</u>
					Cents		
698.06	STEEL/IRON PRICE ADJUSTMENT	100	DC	<u>FIXED PRICE SPECIFICATION</u>	Dollars	\$ <u>1.00</u>	\$ <u>100.00</u>
					Cents		
PLEASE MAKE SURE A BID IS ENTERED FOR EACH ITEM. IF IT IS YOUR INTENT TO BID ZERO, ENTER ZERO.							
SUBTOTAL BASE BID						Dollars	\$ _____
						Cents	\$ _____

Brought Forward \$ _____.

ITEM NUMBER	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE IN WORDS		UNIT PRICE (NUMERALS)	TOTAL (NUMERALS)
699.040001	MOBILIZATION SHALL BE INCLUDED IN THE VARIOUS ITEMS OF THE CONTRACT		NEC	ZERO	Dollars	\$ <u>0.0</u>	\$ <u>0.0</u>
					Cents		
TOTAL BASE BID					Dollars	\$ _____	\$ _____
					Cents		

SUBMITTED ON _____, 2022

Firm: _____

By: _____
 (Signature)

 (Printed)

Title: _____