



MVP ARENA

Prepared by Centrica Business Solutions

MVP Arena Parking Garage Solar PV Canopy and EV Placement

November 13, 2024



A large crowd of people is gathered in a dark arena, looking towards a brightly lit stage. The stage features a large screen displaying vibrant, abstract patterns in shades of purple, pink, and yellow. Several spotlights are directed at the stage, creating a dramatic atmosphere. The word "Agenda" is overlaid in white text on the left side of the image.

Agenda

MVP ARENA

- Project Goals
- Solar Photovoltaic (PV) Scope & System Overview
- Electric Vehicle (EV) Charging Scope & Placement Overview
- Project Assumptions
- Financials & Cash Flows
- Next Steps: Project Timeline

Project Goals

Supporting New York's Clean Energy Standard with renewable sourced energy, along with the County's commitment to "going green" and decarbonization. The need for EV charging based on County's clean fleet commitment to allow for full fleet changeover as well as public access to charging. The MVP Arena parking garage is an ideal location for this type of project.



Proposed Project:

- Solar PV
- Electric Vehicle Charging Stations

Estimated Greenhouse Gas (GHG) reduction of 19,142 metric tons of CO₂



Solar PV System

Solar PV: Scope & Overview


Carport canopy
spanning 6th floor
of parking garage
with snow guards

- Ancillary equipment located on ground floor adjacent to southwest side of parking garage
- (1,827) 580W modules for a 1.06 MW DC system
- (12) 60KW inverters for a 720 KW AC system
- Estimated 1.15 GWH generated in Year 1
- Estimated Year 1 Cost Savings using VDER: \$154,552
- NYSERDA NY-Sun Rebate: \$52,983
- Total IRA 40% Direct Pay with Domestic Content Adder: \$1,997,635



Solar PV: Framing Design

- Most cost-effective design the most efficient foundations for this unique project.
- Structural analysis completed August 2023.
- Southwest edge of canopy height 8' with northern edge at approximately 20'.
- Under canopy LED lighting included.
- Framing structure (steel) complies with Domestic Content requirements.
- Column Type – Long Span Super Structure.
- Preliminary design per Occupancy Classification S-2 Low-Hazard Storage Open Parking Garage.
- NYS Building Code 2020.



Solar PV: American Made!

- Silfab 580W Tier I Solar Modules – Manufactured in the USA
- Silfab bifacial module for increased power output.
- Silfab glass is tempered and anti-reflective coated.
- Silfab offers a 30-Year Power Performance Warranty
- Silfab offers a 12-Year Product Workmanship Warranty extendable to 25 Years.
- TerraSmart - Meets the Build America Buy America Act standards.
- TerraSmart steel is 100% sourced and manufactured in Cincinnati, Ohio.
- TerraSmart 20-Year Limited Warranty.



SILFAB
COMMERCIAL **NTC**

NEXT-GENERATION N-TYPE CELL TECHNOLOGY

Manufactured exclusively in the USA.

- Improved Shade Tolerance
- Improved Low-Light Performance
- Increased Performance in High Temperatures
- Efficient Bifacial Energy Yield
- Enhanced Durability
- Reduced Degradation Rate
- 25-Year Product Warranty/
30-Year Performance Warranty



SILFABSOLAR.COM



Design
Complete structural design drawings for permitting



Engineering
Engineers licensed to stamp designs and calculations in all 50 U.S. states



Manufacturing
Multiple owned manufacturing facilities located in the United States



Installation
Nationwide network of experienced and specialized installation crews



White Plains, NY project

EV Charging System

EV Placement: Overview

52 EV charging stations installed with infrastructure to support a total of 72 EV charging stations


- 32 EV charging stations for County fleet on bottom floor
- 4 public EV charging stations per floor (floors 2-6) with infrastructure to support a total of 8 per floor
- 48A Stations, able to output maximum of 9.9kW
- Estimated Rebates: \$488,691
- Estimated IRA Federal Refueling Direct Pay : \$686,407
- Estimated Annual Fuel Cost Savings: \$16,941



EV: Ease of Use

Extended charging cables of 25' to reach to either side of a vehicle

- Cable Management retractable clamp on each pedestal to keep cables off ground
- Currently specifying J1772 port configuration, may adjust to a mix of NACS configurations when available (estimated mid-2025, based on County feedback)
- Fleet stations activated via RFID card
- Public stations payment processing via QR code and EVConnect app
- 5-year O&M and software services included



Project Assumptions and Considerations



1. Centrica included Davis-Bacon labor rates for this County project with apprenticeship requirements on labor.
2. Project requires new National Grid services to be installed; the solar project is considered a “Behind-the-Meter” interconnection with upgrades as per the National Grid CESIR Study.
3. The Parking Garage Structural review determined that the existing structure could support the added weight of the proposed solar canopy, EV vehicles, and associated equipment with no structural upgrades.
4. EV – 5 Year Term - 24/7 driver support via app and phone number, 72-hour on-site repair dispatch, Automated alerts to EVConnect Support Team, Real Time Performance Management, Routine Network/Firmware updates and preventative maintenance.
5. NYSERDA - NY-SUN Rebate Block 21 At \$.05/DCW or **\$52,983**
6. National Grid EV Make-Ready Rebate: **\$412,691**
7. NYSERDA EV Rebate: **\$76,000**
8. Avoided utility savings is based on the NYSERDA Value of Distributed Energy (VDER) Calculator V3.1.
9. Inflation Reduction Act (IRA) – Centrica is showing base rate of 30% for EV and 40% for PV.

Project Financials

***Cost includes National Grid costs along with Centrica costs to finish design and build**

****The County could be eligible for an extra 10% Direct Pay based on low-income area. Source: U.S. Department of Energy**

*****Centrica to provide annual O&M services on solar PV system**

*Total Investment	\$7,921,747
Rebates Available	\$541,674
CEC Grant	\$830,000
**Solar PV IRA Direct Pay Value	\$1,997,635
EV IRA Refueling Property Direct Pay Value	\$687,290
Net Project Investment (After Rebates and Credits)	\$3,865,148
Annual Cost Savings	\$168,392
***Annual O&M Services	(\$8,954)
30-Year Net Benefits	\$3,288,383

Cash Purchase - Cash Flow

Year	UTILITY COST SAVINGS		Financial Impact						Inflation Reduction Act		PROJECT CASH FLOW	
	Solar kWh	\$/kWh Avoided Cost	IGA Capital Cost	Solar O&M Costs	State Incentives	EV Fuel Cost Savings	NYSERDA CEC Grant	Solar PV Avoided Cost Savings	40% IRA Solar PV Direct Pay	IRA EV Direct Pay	Annual	Cumulative
1	1,157,693	\$0.1335	\$ (7,921,747)	\$ (8,954)	\$ 541,674	\$ 8,471	\$ 830,000	\$ 154,552	\$ 1,997,635	\$ 687,290	\$ (3,690,829)	\$ (3,690,829)
2	1,134,539	\$0.1355	\$ -	\$ (9,223)	\$ -	\$ 16,942		\$ 153,730	\$ -	\$ -	\$ 182,307	\$ (3,508,522)
3	1,130,795	\$0.1372	\$ -	\$ (9,499)	\$ -	\$ 17,450		\$ 155,145	\$ -	\$ -	\$ 184,579	\$ (3,323,943)
4	1,127,064	\$0.1368	\$ -	\$ (9,784)	\$ -	\$ 17,974		\$ 154,182	\$ -	\$ -	\$ 184,500	\$ (3,139,443)
5	1,123,344	\$0.1404	\$ -	\$ (10,078)	\$ -	\$ 18,513		\$ 157,718	\$ -	\$ -	\$ 188,944	\$ (2,950,499)
6	1,119,637	\$0.1423	\$ -	\$ (10,380)	\$ -	\$ 19,068		\$ 159,324	\$ -	\$ -	\$ 191,488	\$ (2,759,011)
7	1,115,942	\$0.1442	\$ -	\$ (10,692)	\$ -	\$ 19,640		\$ 160,919	\$ -	\$ -	\$ 194,047	\$ (2,564,964)
8	1,112,260	\$0.1464	\$ -	\$ (11,012)	\$ -	\$ 20,230		\$ 162,835	\$ -	\$ -	\$ 196,957	\$ (2,368,007)
9	1,108,589	\$0.1480	\$ -	\$ (11,343)	\$ -	\$ 20,837		\$ 164,071	\$ -	\$ -	\$ 199,217	\$ (2,168,790)
10	1,104,931	\$0.1500	\$ -	\$ (11,683)	\$ -	\$ 21,462		\$ 165,740	\$ -	\$ -	\$ 201,940	\$ (1,966,850)
11	1,101,285	\$0.1520	\$ -	\$ (12,033)	\$ -	\$ 22,105		\$ 167,395	\$ -	\$ -	\$ 204,682	\$ (1,762,168)
12	1,097,650	\$0.1541	\$ -	\$ (12,394)	\$ -	\$ 22,769		\$ 169,148	\$ -	\$ -	\$ 207,553	\$ (1,554,615)
13	1,094,028	\$0.1565	\$ -	\$ (12,766)	\$ -	\$ 23,452		\$ 171,215	\$ -	\$ -	\$ 210,773	\$ (1,343,843)
14	1,090,418	\$0.1587	\$ -	\$ (13,149)	\$ -	\$ 24,155		\$ 173,049	\$ -	\$ -	\$ 213,793	\$ (1,130,050)
15	1,086,820	\$0.1605	\$ -	\$ (13,544)	\$ -	\$ 24,880		\$ 174,435	\$ -	\$ -	\$ 216,401	\$ (913,649)
16	1,083,233	\$0.1628	\$ -	\$ (13,950)	\$ -	\$ 25,626		\$ 176,350	\$ -	\$ -	\$ 219,575	\$ (694,073)
17	1,079,658	\$0.1651	\$ -	\$ (14,369)	\$ -	\$ 26,395		\$ 178,252	\$ -	\$ -	\$ 222,773	\$ (471,300)
18	1,076,095	\$0.1674	\$ -	\$ (14,800)	\$ -	\$ 27,187		\$ 180,138	\$ -	\$ -	\$ 225,996	\$ (245,304)
19	1,072,544	\$0.1701	\$ -	\$ (15,244)	\$ -	\$ 28,003		\$ 182,440	\$ -	\$ -	\$ 229,673	\$ (15,631)
20	1,069,005	\$0.1722	\$ -	\$ (15,701)	\$ -	\$ 28,843		\$ 184,083	\$ -	\$ -	\$ 232,733	\$ 217,102
21	1,065,477	\$0.1747	\$ -	\$ (16,172)	\$ -	\$ 29,708		\$ 186,139	\$ -	\$ -	\$ 236,249	\$ 453,350
22	1,061,961	\$0.1772	\$ -	\$ (16,657)	\$ -	\$ 30,599		\$ 188,180	\$ -	\$ -	\$ 239,793	\$ 693,143
23	1,058,457	\$0.1797	\$ -	\$ (17,157)	\$ -	\$ 31,517		\$ 190,205	\$ -	\$ -	\$ 243,366	\$ 936,509
24	1,054,964	\$0.1827	\$ -	\$ (17,671)	\$ -	\$ 32,463		\$ 192,742	\$ -	\$ -	\$ 247,498	\$ 1,184,007
25	1,051,482	\$0.1853	\$ -	\$ (18,202)	\$ -	\$ 33,437		\$ 194,840	\$ -	\$ -	\$ 251,239	\$ 1,435,246
26	1,048,013	\$0.1881	\$ -	\$ (18,748)	\$ -	\$ 34,440		\$ 192,940	\$ -	\$ -	\$ 351,031	\$ 1,786,276
27	1,044,554	\$0.1908	\$ -	\$ (19,310)	\$ -	\$ 35,473		\$ 300,732	\$ -	\$ -	\$ 360,566	\$ 2,146,842
28	1,041,107	\$0.1936	\$ -	\$ (19,889)	\$ -	\$ 36,537		\$ 308,732	\$ -	\$ -	\$ 370,361	\$ 2,517,203
29	1,037,671	\$0.1963	\$ -	\$ (20,486)	\$ -	\$ 37,633		\$ 316,945	\$ -	\$ -	\$ 380,422	\$ 2,897,625
30	1,034,247	\$0.1991	\$ -	\$ (21,101)	\$ -	\$ 38,762		\$ 325,376	\$ -	\$ -	\$ 390,758	\$ 3,288,383
Total	32,583,466		\$ (7,921,747)	\$ (425,990)	\$ 541,674	\$ 774,569	\$ 830,000	\$ 5,841,550	\$1,997,635	\$ 687,290	\$ 3,288,383	

Bond Financing - Cash Flow

	UTILITY COST SAVINGS		Financial Impact						Inflation Reduction Act		PROJECT CASH FLOW	
Year	Solar kWh	\$/kWh Avoided Cost	O&M Costs	Bond Payment	State Incentives	NYSERDA CEC Grant	EV Fuel Cost Savings	Solar PV Avoided Cost Savings	34% IRA Solar PV Direct Pay	IRA EV Direct Pay	Annual	Cumulative
1	1,157,693	\$0.1335	\$ (8,954)	\$ (576,051)	\$ 541,674	\$ 830,000	\$ 8,471	\$ 154,552	\$ 1,697,990	\$ 687,290	\$ 2,667,932	\$ 2,667,932
2	1,134,539	\$0.1355	\$ (9,223)	\$ (576,051)	\$ -		\$ 16,942	\$ 153,730			\$ (393,744)	\$ 2,274,188
3	1,130,795	\$0.1372	\$ (9,499)	\$ (576,051)	\$ -		\$ 17,450	\$ 155,145			\$ (391,471)	\$ 1,882,717
4	1,127,064	\$0.1368	\$ (9,784)	\$ (576,051)	\$ -		\$ 17,974	\$ 154,182			\$ (391,551)	\$ 1,491,165
5	1,123,344	\$0.1404	\$ (10,078)	\$ (576,051)	\$ -		\$ 18,513	\$ 157,718			\$ (387,106)	\$ 1,104,059
6	1,119,637	\$0.1423	\$ (10,380)	\$ (576,051)	\$ -		\$ 19,068	\$ 159,324			\$ (384,563)	\$ 719,496
7	1,115,942	\$0.1442	\$ (10,692)	\$ (576,051)	\$ -		\$ 19,640	\$ 160,919			\$ (382,003)	\$ 337,493
8	1,112,260	\$0.1464	\$ (11,012)	\$ (576,051)	\$ -		\$ 20,230	\$ 162,835			\$ (379,094)	\$ (41,601)
9	1,108,589	\$0.1480	\$ (11,343)	\$ (576,051)	\$ -		\$ 20,837	\$ 164,071			\$ (376,834)	\$ (418,435)
10	1,104,931	\$0.1500	\$ (11,683)	\$ (576,051)	\$ -		\$ 21,462	\$ 165,740			\$ (374,111)	\$ (792,545)
11	1,101,285	\$0.1520	\$ (12,033)	\$ (576,051)	\$ -		\$ 22,105	\$ 167,395			\$ (371,369)	\$ (1,163,914)
12	1,097,650	\$0.1541	\$ (12,394)	\$ (576,051)	\$ -		\$ 22,769	\$ 169,148			\$ (368,498)	\$ (1,532,412)
13	1,094,028	\$0.1565	\$ (12,766)	\$ (576,051)	\$ -		\$ 23,452	\$ 171,215			\$ (365,278)	\$ (1,897,691)
14	1,090,418	\$0.1587	\$ (13,149)	\$ (576,051)	\$ -		\$ 24,155	\$ 173,049			\$ (362,258)	\$ (2,259,948)
15	1,086,820	\$0.1605	\$ (13,544)	\$ (576,051)	\$ -		\$ 24,880	\$ 174,435			\$ (359,650)	\$ (2,619,598)
16	1,083,233	\$0.1628	\$ (13,950)	\$ (576,051)	\$ -		\$ 25,626	\$ 176,350			\$ (356,475)	\$ (2,976,074)
17	1,079,658	\$0.1651	\$ (14,369)	\$ (576,051)	\$ -		\$ 26,395	\$ 178,252			\$ (353,277)	\$ (3,329,351)
18	1,076,095	\$0.1674	\$ (14,800)	\$ (576,051)	\$ -		\$ 27,187	\$ 180,138			\$ (350,055)	\$ (3,679,406)
19	1,072,544	\$0.1701	\$ (15,244)	\$ (576,051)	\$ -		\$ 28,003	\$ 182,440			\$ (346,378)	\$ (4,025,783)
20	1,069,005	\$0.1722	\$ (15,701)	\$ (576,051)	\$ -		\$ 28,843	\$ 184,083			\$ (343,318)	\$ (4,369,101)
21	1,065,477	\$0.1747	\$ (16,172)	\$ -	\$ -		\$ 29,708	\$ 186,139			\$ 236,249	\$ (4,132,853)
22	1,061,961	\$0.1772	\$ (16,657)	\$ -	\$ -		\$ 30,599	\$ 188,180			\$ 239,793	\$ (3,893,060)
23	1,058,457	\$0.1797	\$ (17,157)	\$ -	\$ -		\$ 31,517	\$ 190,205			\$ 243,366	\$ (3,649,694)
24	1,054,964	\$0.1827	\$ (17,671)	\$ -	\$ -		\$ 32,463	\$ 192,742			\$ 247,498	\$ (3,402,196)
25	1,051,482	\$0.1853	\$ (18,202)	\$ -	\$ -		\$ 33,437	\$ 194,840			\$ 251,239	\$ (3,150,957)
26	1,048,013	\$0.1881	\$ (18,748)	\$ -	\$ -		\$ 34,440	\$ 192,940			\$ 643,970	\$ (2,506,987)
27	1,044,554	\$0.1908	\$ (19,310)	\$ -	\$ -		\$ 35,473	\$ 300,732			\$ 661,298	\$ (1,845,689)
28	1,041,107	\$0.1936	\$ (19,889)	\$ -	\$ -		\$ 36,537	\$ 308,732			\$ 679,093	\$ (1,166,596)
29	1,037,671	\$0.1963	\$ (20,486)	\$ -	\$ -		\$ 37,633	\$ 316,945			\$ 697,367	\$ (469,229)
30	1,034,247	\$0.1991	\$ (21,101)	\$ -	\$ -		\$ 38,762	\$ 325,376			\$ 716,133	\$ 246,904
Total	32,583,466		\$ (425,990)	\$ (11,521,015)	\$ 541,674	\$ 830,000	\$ 774,569	\$5,841,550	\$ 1,697,990	\$ 687,290	\$ 246,904	

Next Steps: Project Timeline

MVP Arena milestones to Close plan / Timeline	Owner	Date	Albany County	Centrica	National Grid
National Grid deliver CEISR Study results	National Grid	9/9/2024			x
National Grid provides EV make-ready work costs	National Grid	11/7/2024			x
IGA Approval	Centrica	11/8/2024		x	
Present UESC Proposal to County	Centrica	11/13/2024		x	
PW Committee Meeting - Project Introduction	Albany County	11/26/2024	x		
Leg. Approval	Albany County	12/9/2024	x		
National Grid Task Order execution	Albany County/Centrica/National Grid	12/16/2024	x	x	x
National Grid Interconnection - Deposit	Centrica/National Grid	12/20/2024		x	x
Prepare 100% design docs - carport & electrical (KMB)	Centrica	2/17/2025		x	
Interconnection Pre-work begins	Centrica	2/17/2025		x	x
Subcontractor Contracts	Centrica	3/10/2025		x	

Thank you

Mitch Tombs | Senior Account Executive
P: 315-532-7584
Mitch.Tombs@centrica.com

Jeff Kilmer | Project Director
P: 518-406-0360
Jeff.Kilmer@centrica.com

Scott Clark | Project Director
P: 518-406-0739
Scott.Clark@centrica.com

Eric Toussaint | Dir. of Electrical Solutions
P: 916-531-0328
Eric.Toussaint@centrica.com

Additional Documentation

Equipment & Systems Warranties

- Silfab Modules: **30-Year** Power Performance Warranty
12-Year Product Warranty, extendable to 25-Years
- TerraSmart Canopy: 20-Year Limited Warranty
- Chint Power Systems Inverters: 10-Year Warranty
- EV Equipment: 5-Year Material & Labor
- EV O&M and Software: 5-Year prepaid software and service
- Centrica Solar PV Workmanship Warranty: 5-Years

centrica
Business Solutions



GHG Reductions

19,142 metric tons of CO₂ offset over the lifetime of the system,
equivalent to:




O&M Services

System Monitoring and Dashboard

All projects that Centrica installs under this initiative will have full monitoring and production reporting capabilities via the easy to access Also-Energy Power Track Dashboard. Both Centrica and Also-Energy will monitor the system(s) to ensure maximum performance. Offering NYP piece of mind that their renewable generation assets are accomplishing what they were put in service to do.

Figure 7: Also-Energy Power Track Dashboard



Project Timeline – Full Schedule

MVP Arena milestones to Close plan / Timeline	Owner	Date	Albany County	Centrica	National Grid
National Grid deliver CEISR Study results	National Grid	9/9/2024			x
National Grid provides EV make-ready work costs	National Grid	11/7/2024			x
IGA Approval	Centrica	11/8/2024		x	
Present UESC Proposal to County	Centrica	11/13/2024		x	
PW Committee Meeting - Project Introduction	Albany County	11/26/2024	x		
Leg. Approval	Albany County	12/9/2024	x		
National Grid Task Order execution	Albany County/Centrica/National Grid	12/16/2024	x	x	x
National Grid Interconnection - Deposit	Centrica/National Grid	12/20/2024		x	x
Prepare 100% design docs - carport & electrical (KMB)	Centrica	2/17/2025		x	
Interconnection Pre-work begins	Centrica	2/17/2025		x	x
Subcontractor Contracts	Centrica	3/10/2025		x	
Submittals					
Structural Shop drawings	Centrica	3/31/2025		x	
MV Equipment	Centrica	3/31/2025		x	
LV Equipment	Centrica	3/31/2025		x	
Wire and Conduit Runs	Centrica	4/28/2025		x	
Permitting	Centrica	5/12/2025		x	
Major Equipment Procurement				x	
Structural	Centrica	6/24/2025		x	
Solar Panels	Centrica	7/23/2025		x	
MV Yard Equipment	Centrica	12/8/2025		x	
PV Yard Equipment	Centrica	12/8/2025		x	
EV Chargers	Centrica	12/8/2025		x	
Construction				x	
Mobilization	Centrica	6/10/2025		x	
Structural Steel Erection Start	Centrica	6/25/2025		x	
Structural Steel Erection Complete	Centrica	8/25/2025		x	
PV Panel Installation Complete	Centrica	9/3/2025		x	
Canopy Lighting Complete	Centrica	9/25/2025		x	
PV Low Voltage Work Start	Centrica	9/25/2025		x	
PV Low Voltage Work Complete	Centrica	12/31/2025		x	
MV Electrical Installation Start	Centrica	6/25/2025		x	
MV Electrical Install Complete	Centrica	3/17/2026		x	
Interconnection EV	Centrica	3/24/2026		x	x
Interconnection PV	Centrica	3/31/2026		x	x
Commissioning and Billing Set up	Centrica	4/14/2026	x	x	
Closeout	Centrica	5/7/2026	x	x	x

Spec Sheets

SILFAB COMMERCIAL NTC

SIL-580 XM+
BIFACIAL



NEXT-GENERATION N-TYPE CELL TECHNOLOGY

Manufactured exclusively in the USA.

- Improved Shade Tolerance
- Improved Low-Light Performance
- Increased Performance in High Temperatures
- Efficient Bifacial Energy Yield
- Enhanced Durability
- Reduced Degradation Rate
- 25-Year Product Warranty/
30-Year Performance Warranty



SILFABSOLAR.COM



ELECTRICAL SPECIFICATIONS		580		
Test Conditions		STC	BSTC	NOCT
Module Power (P _{max})	Wp	580	632.8	428.2
Maximum power voltage (V _{pmx})	V	44.27	44.27	40.73
Maximum power current (I _{pmx})	A	13.10	14.29	10.51
Open circuit voltage (V _{oc})	V	52.27	52.32	48.08
Short circuit current (I _{sc})	A	13.85	15.11	11.12
Module efficiency	%	22.4%		
Maximum system voltage (VDC)	V	1500		
Series fuse rating	A	30		
Power Tolerance	Wp	0 to +10		
Bifaciality Factor	%	80±5		


Performance conditions: Measurement tolerance ± 3% - Standard Test Conditions (STC): 1000 W/m², AM 1.5, Temperature 25 °C - Nominal Operating Cell Temperature (NOCT): 800 W/m², AM 1.5 - Bifacial Standard Test Conditions (BSTC): 1000 W/m² + q = 125 W/m², φ = 30°, AM 1.5 - Electrical characteristics may vary by ± 5%.

MECHANICAL PROPERTIES / COMPONENTS	METRIC	IMPERIAL
Module weight	28.5 kg ± 0.2 kg	62.8 lbs ± 0.4 lbs
Dimensions (H x L x D)	2278 mm x 1133 mm x 35 mm	89.7 in x 44.6 in x 1.4 in
Maximum surface load (wind/snow)*	2400 Pa rear load / 2400 Pa front load	50.1 lb/ft ² rear load / 112.0 lb/ft ² front load
Hail impact resistance	± 25 mm at 83 km/h	± 1 in at 51.6 mph
Cells	144 Half-cells - N-Type Silicon solar cell 182 mm ± 0.1 mm	144 Half-cells - N-Type Silicon solar cell 7.16 in ± 0.04 in
Glass	3.2 mm high transmittance, tempered, anti-reflective coating	0.126 in high transmittance, tempered, anti-reflective coating
Cables and connectors (refer to installation manual)	1300 mm, ø 5.7 mm, EVD2 from Staubli	52.1 in, ø 0.22 in (12 AWG), EVD2 from Staubli
Backsheet	High durability, superior hydrolysis and UV resistance, multi-layer dielectric film, transparent PV backsheet	
Frame	Anodized Aluminum (Silver)	
Junction Box	UL 3730 Certified, IEC 62730 Certified, IP68 rated, 3 diodes	

TEMPERATURE RATINGS		WARRANTIES	
Temperature Coefficient I _{sc}	0.04 %/°C	Module product workmanship warranty	25 years**
Temperature Coefficient V _{oc}	-0.24 %/°C	Linear power performance guarantee	30 years
Temperature Coefficient P _{max}	-0.29 %/°C		± 0% end 1st yr ± 0.47% end 12th yr ± 0.90% end 25th yr ± 0.92% end 30th yr
NOCT (± 2°C)	45 °C		
Operating temperature	-40° to 85 °C		

CERTIFICATIONS		SHIPPING SPECS	
Product	UL 61215***, UL 61730***, CSA C22.2 961.1730***, IEC 61215***, IEC 61730***, IEC 61701 (Salt Mist Corrosion), IEC 62716 (Ammonia Corrosion), CEC Listing***, UL Fire Rating: Type 1	Modules Per Pallet:	20
Factory	ISO9001:2015	California (Pallets per load)	21
		Others (Pallets per load)	22

* Warning: Read the Safety and Installation Manual for mounting specifications and before handling, installing and operating modules.
** 12 year extendable to 25 years subject to registration and conditions outlined under "Warranty" at silfab.com.
*** PNM files generated from 3rd party performance data are available for download at: silfab.com/downloads.
*** Certification and CEC listing in progress.



SILFAB SOLAR INC.

1770 Port Drive
Burlington WA 98233 USA
T +1 360.569.4733
info@silfabsolar.com
SILFABSOLAR.COM

7149 Logistics Lane
Port Mill SC 29715 USA
T +1 830.400.4338

240 Courtneyspark Drive East
Mississauga ON L5T 2S5 Canada
T +1 905.255.2501
F +1 905.696.0267

Silfab - SIL-580 XM+ BIFACIAL 20240629
No reproduction of any kind is allowed without permission. Data and information is subject to modifications without notice. © Silfab Solar Inc., 2024. Silfab Solar® is a registered trademark of Silfab Solar Inc.

50/60 kW, 1000 Vdc String Inverters for North America

The 50 & 60 kW (55 & 66 kVA) medium-power CPS three-phase string inverters are designed for ground mount, large rooftop and carport applications. The units are high performance, advanced and reliable inverters designed specifically for the North American environment and grid. High efficiency at 98.8% peak and 98.5% CEC, wide operating voltages, broad temperature ranges and a NEMA Type 4X enclosure enable this inverter platform to operate at high performance across many applications.

The CPS 50/60KTL products ship with either the Standard Wire-box or the Rapid Shutdown Wire-box, each fully integrated and separable with touch-safe fusing, monitoring, and AC and DC disconnect switches. The integrated PLC transmitter in the Rapid Shutdown Wire-box enables PVRSS certified module-level rapid shutdown when used with APS RSD-S-PLC/RSD-D products. The CPS FlexOM Gateway enables monitoring, controls and remote product upgrades.

Key Features

- NEC 2017/2020 PVRSS certified for rapid shutdown
- 55 & 66 kVA rating allows max rated active power @ ±0.91 PF
- Selectable max AC apparent power of 50/55 kVA and 60/66 kVA
- NEC compliant and UL listed arc-fault circuit protection
- 15-90° mounting orientation for low profile roof installs
- Optional FlexOM Gateway enables remote firmware upgrades
- Integrated AC and DC disconnect switches
- 3 MPPTs with 5 inputs each for maximum flexibility
- NEMA Type 4X outdoor rated enclosure
- UL 1741-SA certified to CA Rule 21, including SA8 - SA18
- UL 1741-SB and IEEE 1547-2018 certified
- Separable wire-box design for fast service
- Standard 10-year warranty with extensions up to 20 years



CPS SCA50KTL-DO/US-480
CPS SCA60KTL-DO/US-480



50/60KTL Standard Wire-box



50/60KTL Rapid Shutdown Wire-box



Model Name	CPS SCA50KTL-DO/US-480	CPS SCA60KTL-DO/US-480
DC Input		
Max PV power	90 kW (33 kW per MPPT)	
Max DC input voltage	1000 Vdc	
Operating DC input voltage range	200-950 Vdc	
Start-up DC input voltage / power	330 V / 80 W	
Number of MPPT trackers	3	
MPPT voltage range @ PF>0.99	480-850 Vdc	540-850 Vdc
Max PV short-circuit current (Isc x 1.25)	204 A (68 A per MPPT)	
Number of DC inputs	15 Inputs, 5 per MPPT	
DC disconnection type	Load-rated DC switch	
DC surge protection	Type II MOV	
AC Output		
Rated AC output power @ PF>0.99 to ±0.91 ¹	50 kW	60 kW
Max AC apparent power (selectable)	50 / 55 kVA	60 / 66 kVA
Rated output voltage	480 Vac	
Output voltage range ²	422 - 528 Vac	
Grid connection type	3Ø / PE / N (Neutral optional)	
Max AC output current @ 480 Vac	60.2 / 66.2 A	72.2 / 79.4 A
Rated output frequency	60 Hz	
Output frequency range ³	57 - 63 Hz	
Power factor	>0.99 (±0.8 adjustable)	
Current THD @ rated load	<3%	
Max fault current contribution (1 cycle RMS)	64.1 A (1.06/0.88 PU)	
Max OCPD rating	110 A	125 A
AC disconnection type	Load-break rated AC switch	
AC surge protection	Type II MOV	
System and Performance		
Topology	Transformerless	
Max efficiency	98.8%	
CEC efficiency	98.5%	
Stand-by / night consumption	<1 W	
Environment		
Enclosure protection degree	NEMA Type 4X	
Cooling method	Variable speed cooling fans	
Operating temperature range ³	-22°F to +140°F / -30°C to +60°C	
Non-operating temperature range ⁴	No low temp minimum to +158°F / +70°C maximum	
Operating humidity	0 to 100%	
Operating altitude	13123 ft / 4000 m (derating from 9843 ft / 3000 m)	
Audible noise	<60 dBA @ 1 m and 25°C	
Display and Communication		
User interface and display	LCD+LED	
Inverter monitoring	SunSpec, Modbus RS485	
Site-level monitoring	CPS FlexOM Gateway (1 per 32 inverters)	
Modbus data mapping	CPS	
Remote diagnostics / firmware upgrade functions	Standard / (with FlexOM Gateway)	
Mechanical		
Dimensions (H x W x D)	39.4 x 23.5 x 10.24 in (1000 x 600 x 260 mm)	
Weight	Inverter: 123.5 lbs (56 kg); Wire-box: 33 lbs (15 kg)	
Mounting / installation angle ⁵	15 to 90 degrees from horizontal (vertical or angled)	
AC termination	M8 stud type terminal block (wire range: #6 - 3/0 AWG CU/AL; lugs not supplied)	
DC termination ⁶	Screw clamp, neg. busbar (RSD version ⁷) wire range: #14 - #6 AWG CU	
Fused string inputs (5 per MPPT) ⁷	RSD ⁸ and Standard Wire-box 20 A fuses provided (fuse values up to 30 A acceptable)	
Safety		
Certifications and standards	UL 1741-SA/SB Ed. 3, UL 1699B, UL 1998, CSA-C22.2 NO.107.1-01, IEEE 1547-2018, FCC PART15	
Selectable grid standard	IEEE 1547a-2014, IEEE1547-2018 ⁹ , CA Rule 21, ISO-NE, HECCO	
Smart-grid features	Volt-RideThru, Freq-RideThru, Ramp-Rate, Specified-PF, Volt-VAR, Freq-Watt, Volt-Watt	
Warranty		
Standard	10 years	
Extended terms	15 and 20 years	

1) Active power derating begins at PF = ±0.91 to ±0.80 when max AC apparent power is set to 55 or 66 kVA.

2) The "output voltage range" and "output frequency range" may differ according to the specific grid standard.

3) Active power derating begins at 40°C when PF = ±0.9 and MPPT voltage; at 40°C when PF = 1 and MPPT voltage; and at 50°C when PF = 1 and MPPT voltage.

4) See user manual for further requirements regarding non-operating conditions.

5) Shade cover accessory required for installation angles of 75 degrees or less.

6) RSD wire-box only includes fuses and fuse holders on the positive polarity, compliant with NEC 2017/2020.

7) Fuse values above 20 A have additional spacing requirements or require the use of the Y-Comb Terminal Block. See user manual for more details.

8) Firmware version 17.0 or later required.

Garage Canopy



Building a solar canopy on top of a parking garage is an effective way to increase the presence of renewable energy systems in urban environments. Beyond the benefit of solar, canopies also provide shading for vehicles parked on the top level of the garage. Canopy structures are designed to be minimally invasive, meaning existing parking spaces will not be impacted in any way.



Collaborative Design

- With backgrounds in architectural engineering, our team of designers is there to assist you beginning at the conceptual design phase of a project.
- Whether the project is being planned on an existing parking garage or one that is going to be constructed, our team can generate custom design specifications to meet any unique project requirements.
- In collaboration with our experienced project management team, we can run through multiple design options on a project to achieve a specific project goal.
- As licensed structural engineers, our team can provide signed and sealed drawings, along with any other documentation required for permitting.

Full Project Support Staff

- Customized features such as underdecking, water management, and finishing can transform any structure into an aesthetic focal point.
- Our scope of services can include full structural installation, beginning at the columns and all the way through attaching PV modules.
- Dedicated project managers provide material delivery and installation schedules, along with daily construction updates throughout the process.
- Structural installation is minimally invasive, allowing parking garages to remain operational during construction.

AlsoEnergy Commercial & Industrial Solution

Pull all data onto a single, shared platform for a 360° view of project and portfolio performance and the power to optimize outcomes.



Optimize energy harvest

- Improve understanding of projects and portfolio
- Identify and address areas of low performance
- Utilize advanced diagnostics and analytics

Streamline workflow

- Integrate project design data, track activities, report on performance
- Extend to all management systems
- Stay connected with mobile apps

Avoid unnecessary costs

- Identify and address high-impact issues first
- Automate repetitive tasks
- Avoid truck rolls leveraging smart two-way communications technology

Maximize value

Home in on key performance indicators to manage project lifecycles and portfolios more effectively

Optimize financial process

- Combined financial and management data
- Unified recordkeeping
- On-the-fly analysis

Simplify accounting

- Protect assets
- Improve performance
- Monitor entire chain of responsibility

Mitigate risk

- Manage risk and compliance
- Cross-portfolio analysis
- Audit trails to maintain data quality

Keep collaborative work on track and under control

Share the latest information to eliminate resource waste.

Expert support

- Accelerate innovation
- Easy, flexible implementation
- On-site, cloud resources

Future-proof platform

- Work with Big Data
- Stable and reliable architecture
- Enable partnerships and integrations

3rd-party resource management

- Streamline process
- Take advantage of proactive intervention
- Analyze and understand drivers of profitability

One comprehensive view of the entire asset portfolio

Increase productivity and reduce maintenance costs.

Maximum resource uptime

- Pinpoint and address areas of low performance
- Drive maintenance with CMMS
- Analyze and identify poor performance trends early

Exception-based alerting

- Real-time insight, anywhere, anytime
- Minimized nuisance alerts
- Automated or on-demand reports

Management mapping

- Achieve high-performance verification
- Flag deficiencies instantly
- Collaborate throughout the organization

Transform and modernize the supply chain

Open pathways for real-time feedback and resource optimization

Seamless procurement

- End-to-end business process
- Streamline and automate documentation
- Adapt to engineering changes quickly

Optimized commissioning, installation

- Increase productivity
- Reduce waste
- Manage project risk

Specialized O&M service

- Control solutions for O&M sites that need active management
- Accelerate plant validation
- Automate performance analytics

Maximize value with actionable insights

Drive process innovation to make better decisions faster.

Flexible technology platform

- Extend solutions around machine learning, other emerging technologies
- Scale up service as your business grows
- Expand built-in performance modeling capability

Optimized design

- Detailed historical and real-time analysis
- Rapid retrieval of commonly used charts and reports

Unparalleled decision support

- View projects and portfolios from all angles
- Leverage real-time data
- Increase productivity

To find out more or schedule a demo, contact us at alsoenergy.com

Harmonize data to attain operational excellence

Knock down data silos, bringing all project and portfolio information together to form a single version of the truth.

Practice proactive management

- Empower users to manage large portfolios
- Identify and apply corrective actions quickly
- Tie costs back to specific events

Control the health of your portfolio

- Rapid response time
- Notifications on occurrence or schedule
- Device, plant, or portfolio-level diagnosis

Run the business your way

- Custom displays to match business needs
- A single platform to manage all sites
- Third-party software integration

Intelligent planning, maintenance and documentation

Get the right information to the right person at the right time for efficient service in the field.

Act quickly and efficiently

- Simplify processes
- Schedule and report on tickets directly
- Use field technician-focused mobile app

Accurate alerts

- Scheduled maintenance or an immediate truck roll
- Priority for maintenance technician activities
- Easy alert-to-ticket creations

Specialized customer support

- Remote and on-site training
- Localized support from regional offices
- Extensible architecture supports third-party integration

AlsoEnergy Commercial & Industrial Solution Components

Software

- PowerTrack Web
- Analytics
- Diagnostics
- Reports
- PowerTrack Mobile
- CMMS Solutions
- Asset Management Solutions
- Portfolio Aggregation Solutions
- Public display
- Cybersecurity and remote access solutions
- Export control supervisory dashboards

Hardware

- PowerLogger 1000 / dataloggers
- Weather stations / sensors
- Revenue-grade meters
- Field I/O
- Site Controllers
- UPS
- Cell modem & plan
- Networking equipment
- Weatherproof enclosures

Professional Services

- Expert support
- Portfolio aggregation / site migration
- Hardware testing, configuration, assembly, support
- Hardware warranty management
- Third-party hardware integration
- Third-party API app integration
- Agency reporting
- Software configuration and customization
- System modeling
- System engineering
- On-site or remote commissioning support
- Switchgear interfacing
- Telemetry
- Project management
- Project consultation and planning
- Deployment and implementation management
- SCADA system design

AX SERIES



ZEROVA

FEATURES

-  Residential and Commercial EV Charging
-  Wired/Wireless Connection for Central Management System
-  Supports RFID Card, QR Code and Optional Third Party Payment System
-  Input: 200Vac~240Vac
-  Modern, Ergonomic and Customizable Design
-  5-Inch LCD Display, Optional Non-Display
-  IP56/NEMA 4 Rated for Indoor/Outdoor Applications
-  Charging Interface: SAE J1772 (Type 1)/IEC 62196-2 (Type 2)
-  OCPP 1.6 J2818 (Upgradeable to 2.0 OTA)
-  ISO 15118 Protocol (Plug&Charge, Bi-Directional)
-  OCPP or Local Load Management (Parent/Child)
-  Over the Air Technology
-  Energy Star, CTEP and NTEP (NIST Handbook 44)



For information on the optional pedestal, please refer to the accessory section.

INDUSTRY



Residential/MUD



Commercial




Retail



Parking + Fleet

EV WALL MOUNT AC CHARGER

SPECIFICATION

Model Name	AXLU111
Safety	UL/Cul
Outline (in)	

Power Specification

AC Input	Input Rating	Single Phase: 200~240Vac
	AC Input Connection	L1, L2, GND or L, N, PE
	Input Current	48A
	Frequency	50Hz/60Hz
AC Output	Output Current	48A

User Interface & Control

Display	LED Indicator (Standard), 5" LCD Display (Optional)
User Authentication	RFID, Smart Phone App, QR Code Optional Third Party Payment System
Meter	Meter IC (1% Accuracy)

Communication

Vehicle to Grid Communication Interface	ISO 15118 (Plug&Charge, Bi-Directional)
Network Interface	Ethernet + Wi-Fi (IEEE802.11 b/g/n) (standard) Ethernet + Wi-Fi (IEEE802.11 b/g/n) + 4G (optional)
Charging Protocol	OCPP 1.6 JSON (Upgradeable to 2.0 OTA)

Environmental

Operating Temperature	-22°F~122°F (-30°C to +50°C)
Humidity	< 85% (RH) @ 122°F (50°C)
Altitude	≤6562ft (2000m)
IP Level	NEMA TYPE 4/IPK08
Cooling Method	Natural Cooling

Mechanical

Dimensions (WxDxH)	11 x 7 x 20in (280 x 178 x 508mm)
Weight	<22lbs (10kg)
Cable Length	16.4ft (5m) or 25ft (7.5m) with Optional Cable Management

Protection

RCD/OCID	CCID 20
Input	UVP; OVP; Surge Protection, Ground Fault
Output	OCP; Control Pilot Fault, Residual Current Protection
Internal	OTP; Relay Welding Detection, CCID Self-Test, MCU Function Fault Detection

Regulation

Certification	UL2594, UL2231-1/-2 Energy Star CTEP NTEP (NIST Handbook 44)
Wireless Certification	FCC/IC
Charging Interface	SAE J1772 Type 1 Plug